

**Listing of Claims**

This listing of claims will replace all prior version, and listings, of claims in the application:

1-13. (Canceled)

14. (Previously presented) A method for installing a covering system comprising the following steps:

(a) removing a release liner from one or more portions of each of two or more roofing peripherals to expose a pre-applied adhesive on each of the one or more portions of each of the roofing peripherals; and

(b) adhering the two or more peripherals to one or more thermoplastic membranes using the pre-applied adhesive, wherein the one or more thermoplastic membranes are affixed to a building structure.

15-17. (Canceled)

18. (Previously presented) A method for installing a flashing comprising:

providing a universal flashing having a pre-applied adhesive on one or more portions thereof; and

adhering the universal flashing to two or more surfaces that are at one or more angles to each other using the pre-applied adhesive, wherein the two or more surfaces are part of one or more thermoplastic membranes affixed to a building structure.

19. (Previously presented) The method of Claim 18, wherein the universal flashing is adhered to three or more surfaces that are at angles with respect to each other.

20. (Previously presented) The method of Claim 19, wherein at least one of the three surfaces is part of a thermoplastic membrane covering at least part of an exterior corner of the building structure.

21. (Previously presented) The method of Claim 14, wherein the building structure is a roof.
22. (Previously presented) The method of Claim 14, wherein the building structure is a roof and other types of building structures adjacent to or extending from the roof.
23. (Previously presented) The method of Claim 14, wherein the two or more building structure peripherals comprise two or more different types of building structure peripherals.
24. (Previously presented) The method of Claim 14, wherein one or more of the building structure peripherals is a flashing.
25. (Previously presented) The method of Claim 24, wherein the flashing is a semi-rigid flashing.
26. (Previously presented) The method of Claim 24, wherein the flashing is a universal flashing.
27. (Previously presented) The method of Claim 14, wherein one or more of the building structure peripherals is a pipe boot.
28. (Previously presented) The method of Claim 18, wherein said membrane includes a UV absorber and/or a UV screener.
29. (Previously presented) The method of Claim 18, wherein the universal membrane includes a fire retardant.
30. (Previously presented) The method of Claim 18, wherein the universal membrane further comprises a release liner that is releasably bonded to the pre-applied adhesive.

31. (Previously presented) The method of Claim 18, wherein the pre-applied adhesive comprises styrene-ethylene-butylene-styrene.